

# JB-Flexible Deliniator Post

Installation Instruction



Sture Steens väg 2, SE-341 55 Vittaryd  
Tel. +46(0)370-472 00 · info@pekuma.se · www.pekuma.se

## Installation JB Flexible

*Before the work is started you need to make sure there are no existing cables etc. under ground.*

### Installation of post with anchor

A hole is punched / dug at the site, the edge post is lowered to its correct height, then the cavity around the edge post is filled with suggested macadam 2-4 or crushed material 0-18. **Hereafter, the packing of the masses around the post should be carried out very carefully, preferably mechanically with an electric hammer or similar. It is important to pack from all angles to the base of the edge post!**

### Installation of post with ground spike socket

Any existing grass edge should be removed. The socket is then punched or dug down to the correct height. **Packing of surrounding materials is extremely important when installing the post in a spike socket.** When the post is mounted in the socket, it is wedged firmly on the "trench side" with the accompanying wedge. Then the post is screwed tight through the existing holes in the top edge of the socket. Finally, the ground surface next to the socket must be modeled. Depending on the slope of the trench, the socket may either rise above the slope surface (however max 10cm) or fall below.

### Installation of post with stud

A hole is punched / dug at the site and the plastic socket is lowered to the correct height. **Packing of surrounding materials is extremely important when installing the post in a plastic socket.** It is important that this model is also screwed through the socket and post to prevent twisting.

**If in any doubt, feel free to contact us:  
info@pekuma.se or +46 (0)370-47200**

In the same way that a fixed deliniator post needs to be adjusted after impact, hits or plow damage, JB-Flexible also needs supervision to ensure that it does not end up in a constant folded position for an extended period of time.

